



EXTREME UNIVERSE SPACE OBSERVATORY (EUSO)

LENS FABRICATION AT THE MSFC SOMTC

JAMES DRAKE

18-SEPTEMBER 2003



PROJECT EUSO



- Future ISS External Payload
- Employs double sided Fresnel Lens
- Convex, Concave Meniscus
- Final lens diameter to be 2.5 meter





PROJECT EUSO



Prototype Double Fresnel Lens produced at SOMTC
 1.2 Meter Diameter



















- Designed and Built by Moore Tool Company
- Built in 1985
- One of two in existence
- 40-inches of travel in X-Axis
- 30-inches of travel in Z-Axis
- Maximum swing up to 112-inches
- Hydrostatic Spindle with 4000-lbs Capacity
- Laser feedback for positioning
- Positional Accuracy of 100-micro inches over full travel
- Modified in 1998 to accept larger diameter parts












PROTOTYPE FABRICATION PROCESS

- Raw Material: 4.25-inch thick PMMA
- Convex side turned first:
 - Mount on 3 points of equal height
 - Face flat
 - Flip and hold with vacuum
 - Series of Convex Fresnel Facet Cuts
- Concave side turned second








PROTOTYPE FABRICATION PROCESS

- Turning of Concave side required design and fabrication of separate vacuum chuck
- Made from 5-inch thick Aluminum
- Chuck mirrored convex geometry
- Lined with PTFE Skived Film Tape

























- Series of rough dish cuts
- Followed by series of Concave Fresnel Facet Geometry
- Removal from machine







RECENT IMPROVEMENTS AND LESSONS LEARNED

- Diagnosis of spindle shaft errors
- Lapping of spindle thrust surfaces
- Motion control system analysis
- Machine vibration analysis
- Vibration damping methods
- Speeds and feeds testing







RECENT IMPROVEMENTS AND LESSONS LEARNED

Vibration Damping Methods:

- Spring belt tension
- Elastomer damping support









RECENT IMPROVEMENTS AND LESSONS LEARNED

Current Machine Performance:

Surface Finish RMS Improved:

From: 1200 Å

To: Under 400 Å



Following a continuous process of analysis and improvement